
NOTES


- 1. Valve must be installed on supply line to regulate flow.
- Concrete mounting surface for structure installation needs to be level and flat.
- 3. Supply line is based on the designated flow rates for structure.
- 4. Underground plumbing to be designed for winterization.
- 5. Consult local electrical inspector for grounding.
- 6. Concrete to be rated for 4000 psi minimum before installing structure. Approx. 28 days of curing to reach rate.
- 7. Product may require a strainer on the water feed line. Consult with manufacturer.
- 8. Product specifications are subject to change.



level

Thickened slab

SPLASH ZONE



Splash Zone-Not to Scale

Splash Zone Notes:

Splash zones are approximate, actual splash may vary based on various environmental conditions, flow rates, slope of splash pad, submergence depth and wind.

PRODUCT OPTIONS

Structure:

Fiberglass Fabrication (see specification for details)

Skirl

Fiberglass Fabrication (see specification for details)

DATA

Flow: 150 to 300 GPM

Pressure: 4 PSI

Supply Line: 4" to 6" Pipe

Installation: Flange Mount to Concrete

Not for Construction

Slope $\frac{1}{8}$ "/ft



1101 McKinley Parkway Delano, MN 55328 , 888-438-6574 763-972-5200 aquatix.playlsi.com

4 14 44

Water supply (For line size, refer to

Data note)

MINI WATER DOME

DRAWN BY	CTS	SCALE	1/4	'' = 1'- O''	DATE	12/31/18
REVISED BY	NCS	REVISIO LETTER	N	С	REVISION DATE	2/7/2025

This drawing is issued in confidence for engineering information only. This drawing shall remain the property of Aquatix and may not be reproduced, disclosed to a third party, or used to manufacture anything without direct written permission from Aquatix. Unauthorized use shall entitle Aquatix to all damages caused by such user including preparation charges, lost profits, damage to reputation and attorney's fees.